


TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476

OLD BURYING GROUND - PERIMETER WALL REPAIRS



OLD BURYING GROUND - LOCUS PLAN

GENERAL NOTES:


- GOVERNING CODE: MASSACHUSETTS STATE BUILDING CODE, 9TH EDITION.
- STATIONS LISTED WERE NOT SURVEYED AND ARE APPROXIMATE (+/- 10'). STATIONS ARE PROVIDED FOR GENERAL LOCATION REFERENCE FOR REPAIR AREAS ONLY. THESE STATIONS ARE NOT SUITABLE FOR QUANTITY TAKE-OFFS. CONTRACTOR TO TAKE THEIR OWN DIMENSIONS IN THE FIELD PRIOR TO SUBMITTING THEIR BID.
- THE WORK SITE IS A PUBLIC SPACE AND SHALL REMAIN IN PUBLIC USE THROUGHOUT THE PROJECT TO THE EXTENT POSSIBLE. MAINTAIN APPROPRIATE LANGUAGE, CLOTHING AND DECORUM AT ALL TIMES. LIMIT PARKING, PLACEMENT OF MATERIALS, TOOLS, ETC. TO LAY-DOWN AREA AND/OR WORK AREA.

OUTLINE SCOPE OF WORK:

- COMPLETE ALL REQUIRED SUBMITTALS INCLUDING MATERIAL SAMPLES, PRIOR TO THE START OF WORK.
- COMPLETE MOCKUPS AS REQUIRED BY THIS SECTION INCLUDING:
 - MORTAR REMOVAL AND JOINT PREPARATION
 - CLEANING OF THE WALL INCLUDING BRICK, STONE, AND GRANITE
 - REPOINTING
 - LOCALIZED REBUILDING OF MASONRY WALL (BRICK AND STONE WALLS), INCLUDING REMOVING AND RESETTING COPING STONES, MARBLE TOMB MARKERS, AND REPLACING MISSING COPING STONES..
- THE CONTRACTOR MUST IMMEDIATELY CEASE WORK IN THE VICINITY AND WITHOUT DELAY, NOTIFY THE OWNER SHOULD ANY HUMAN REMAINS, OR EVIDENCE THEREOF, BE DISCOVERED DURING THE COURSE OF CONSTRUCTION. PROTECT AREA WHERE REMAINS HAVE BEEN UNCOVERED FOR REVIEW AND DOCUMENTATION BY THE OWNER. RECOMMENCEMENT OF WORK IN THE VICINITY SHALL BE AT THE DIRECTION OF THE OWNER.
- REMOVE ALL STAINING, SOILING, AND BIOLOGICAL GROWTH.
- PRIOR TO REMOVAL, NUMBER ALL COPING STONES, MARBLE TOMB MARKERS, AND LARGE CUT GRANITE STONES WITH AN EASILY REMOVABLE MATERIAL THAT WILL NOT STAIN THE STONES, SUCH AS DUCT TAPE OR CHALK. CAREFULLY REMOVE AND STORE, EXERCISING CARE NOT TO DAMAGE THE STONES. CHIPS AT THE EDGES FROM PRYING ARE NOT PERMISSIBLE. STORE STONES FOR REINSTALLATION IN A PROTECTED AREA, AND DISPOSE OF MORTAR. AS SOON AS EACH STONE IS REMOVED FROM THE WALL, NUMBER IT IN A PERMANENT MANNER, SUCH AS WITH A PAINT MARKER, ON THE CONCEALED UNDERSIDE SURFACE OF THE STONE.
 - THE STONES MAY BE STORED ON-SITE OR OFF-SITE. IF THEY WILL BE STORED ON SITE, PROVIDE PROTECTION FOR THE LANDSCAPING (E.G., PLYWOOD). CONTRACTOR TO PROVIDE STORAGE PLAN PRIOR TO START OF WORK.
- REMOVE THE MORTAR BED JOINTS WHERE INDICATED.
- CLEAN 100% OF ALL MASONRY SURFACES WITHIN THE SCOPE OF WORK, INCLUDING BRICK AND STONE MASONRY, INCLUDING ALL AREAS THAT ARE REBUILT, REPAIRED, OR EXISTING. CLEAN THE BRICK AND STONE IN ACCORDANCE WITH THE PRODUCTS AND METHODS APPROVED DURING THE CLEANING MOCKUPS. MARBLE TOMB MARKERS TO BE REPAIRED AND CLEAN BY OWNER AND RESET BY THE CONTRACTOR.
- PROVIDE NEW REPLACEMENT BRICK FOR FULL HEIGHT REBUILDING WHERE INDICATED ON THE DRAWINGS. SALVAGE EXISTING BRICK IN GOOD CONDITION FOR REUSE AT LOCATIONS OF BRICK REPLACEMENT.
- RESET THE EXISTING COPING STONES. REPAIR DAMAGED STONE FOR RE-USE.
- REMOVE AND REPOINT MORTAR JOINTS WHERE INDICATED ON THE DRAWINGS (INCLUDING AT THE TOP OF THE WALL BENEATH THE COPING STONES) TO A MINIMUM DEPTH OF 2.5x THE JOINT WIDTH OR 3" MAX. , DEEPER WHERE NECESSARY TO REACH SOUND MORTAR. EXERCISE CARE NOT TO DAMAGE ANY EXISTING STONE OR BRICK. \
- PERFORM FINAL WASH-DOWN OF THE WALL.

DRAWING LIST			
DRAWING NO.	DRAWING TITLE	STATION NO.	PHOTOS
S000	COVER	NA	NA
S001	OLD BURYING GROUND SITE PLAN	NA	NA
S1.01	PHASE 1 EXTERIOR	STA. 9+56' TO 8+20'	PHOTO 1 TO 14
S1.02	PHASE 1 INTERIOR	STA. 9+56' TO 8+20'	PHOTO 15 TO 23
S1.03	PHASE 1 EXTERIOR/INTERIOR	STA. 8+20' TO 7+40'	PHOTO 24 TO 37
S2.01	PHASE 2 EXTERIOR	STA. 7+40' TO 5+90'	PHOTO 38 TO 52
S2.02	PHASE 2 INTERIOR	STA. 7+40' TO 5+90'	PHOTO 53 TO 67
S2.03	PHASE 2 EXTERIOR	STA. 5+90' TO 4+96'	PHOTO 68 TO 76
S2.04	PHASE 2 INTERIOR	STA. 5+90' TO 4+96'	PHOTO 77 TO 85
S3.01	PHASE 3 EXTERIOR	STA. 4+48' TO 3+10'	PHOTO 86 TO 99
S3.02	PHASE 3 EXTERIOR	STA. 3+10' TO 1+60'	PHOTO 100 TO 113
S3.03	PHASE 3 EXTERIOR	STA. 1+60' TO 0+00'	PHOTO 114 TO 129
S5.01	REPAIR DETAILS	NA	NA

SIMPSON GUMPERTZ & HEGER
Engineering of Structures
and Building Enclosures



Simpson Gumpertz & Heger Inc.

480 Totten Pond Road

Waltham, Massachusetts 02451

main: 781.907.9000 fax: 781.907.9009

www.sgh.com

Boston

Chicago

Houston

Los Angeles

New York

San Francisco

Washington, DC

Consultant

BID # 20-27

No.	Date	Description	By

OLD BURYING GROUND
&
MT. PLEASANT CEMETERY

TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476

Project

OLD BURYING
GROUND
COVER SHEET

Drawing Title

Project No.
191791.00

Drawn
MAP

Checked
RES


Approved
EWF

Date
2020/05/13

Scale
NTS

Seal

S000



 **SITE PLAN**

SIMPSON GUMPERTZ & HEGER
Engineering of Structures
and Building Enclosures

Simpson Gumpertz & Heger Inc.
480 Totten Pond Road
Waltham, Massachusetts 02451
Main: 781.907.9000 Fax: 781.907.9009
www.sgh.com

Boston
Chicago
Houston
Los Angeles
New York
San Francisco
Washington, DC

Consultant

BID # 20-27

No.	Date	Description	By














**OLD BURYING GROUND
&
MT. PLEASANT CEMETERY**

**TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476**

**OLD BURYING
GROUND
SITE PLAN**

Project No. 191791.00	Checked RES	Date 2020/05/13
Drawn MAP	Approved EWF	Scale NTS
Drawing No. S001		

Seal



REPAIR NUMBER	REPAIR DESCRIPTION	REF. DETAIL/SHEET NUMBER
1	REPORT BRICK MORTAR JOINTS	1/55.01
2	BRICK REPLACEMENT (SINGLE WYTHE)	2/55.01
3	REPAIR BRICK WALL	3/55.01
4	STONE REPORTING	4/55.01
5	DEEP STONE REPOINTING AND RESETTING	5/55.01
6	REPOINT BRICK WALL RE-USING EXISTING STONE	6/55.01
7	REMOVE AND RESET COPING STONES	7/55.01
8	REPLACE MISSING COPING STONE	7/55.01
9	INSTALL NEW COPING STONE STAPLE	8/55.01
10	REMOVE AND RESET MARBLE STONE MASONRY	9/55.01

BID # 20-27

No.	Date	Description	By

**OLD BURYING GROUND
&
MT. PLEASANT CEMETERY**



**TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476**

PHASE 1
STA. 9+56' TO STA. 8+20'
EXTERIOR

Project No. 191791.00	Checked RES	Date 2020/05/13
Drawn MAP	Approved EWF	Scale NTS
Drawing No.		

S1.01

Seal



PHASE 1 STA. 9+56' TO STA. 8+20' INTERIOR




PHOTO 15 (STA. 9+56' TO STA. 9+50')




PHOTO 16 (STA. 9+50' TO STA. 9+40')




PHOTO 17 (STA. 9+40' TO STA. 9+30')




PHOTO 18 (STA. 9+30' TO STA. 9+20')




PHOTO 19 (STA. 9+20' TO STA. 9+10')




PHOTO 20 (STA. 9+10' TO STA. 9+00')



PHOTO 21 (STA. 9+00' TO STA. 8+90')



PHOTO 22 (STA. 8+90' TO STA. 8+80')



PHOTO 23 (STA. 8+80' TO STA. 8+70')

SIMPSON GUMPERTZ & HEGER
Engineering of Structures
and Building Enclosures

Simpson Gumpertz & Heger Inc.
480 Totten Pond Road
Waltham, Massachusetts 02451
Main: 781.907.9000 Fax: 781.907.9009
www.sgh.com

Boston
Chicago
Houston
Los Angeles
New York
San Francisco
Washington, DC

Consultant

REPAIR NUMBER	REPAIR DESCRIPTION	REF. DETAIL/SHEET NUMBER
1	REPOINT BRICK MORTAR JOINTS	1/55.01
2	BRICK REPLACEMENT (SINGLE WYTHE)	2/55.01
3	REBUILD BRICK WALL	3/55.01
4	STONE REPOINTING	4/55.01
5	DEEP STONE REPOINTING AND RESETTling	5/55.01
6	REBUILD STONE WALL RE-USING EXISTING STONE	6/55.01
7	REMOVE AND RESET COPING STONES	7/55.01
8	REPLACE MISSING COPING STONE	7/55.01
9	INSTALL NEW COPING STONE STAPLE	8/55.01
10	REMOVE AND RESET MARBLE TOMB MARKER	9/55.01

BID # 20-27

No.	Date	Description	By

**OLD BURYING GROUND
&
MT. PLEASANT CEMETERY**

**TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476**

Project


**PHASE 1
STA. 9+56' TO STA. 8+20'
INTERIOR**

Drawing Title

Project No. 191791.00	Checked RES	Date 2020/05/13
Drawn MAP	Approved EWF	Scale NTS

Drawing No.
S1.02

Seal



EXTERIOR




PHOTO 26 (STA. 8+00' TO STA. 7+90')




PHOTO 25 (STA. 8+10' TO STA. 8+00')




PHOTO 24 (STA. 8+20' TO STA. 8+10')




PHOTO 29 (STA. 7+70' TO STA. 7+60')




PHOTO 28 (STA. 7+80' TO STA. 7+70')




PHOTO 27 (STA. 7+90' TO STA. 7+80')




PHOTO 31 (STA. 7+50' TO STA. 7+40')





PHOTO 30 (STA. 7+60' TO STA. 7+50')



INTERIOR




PHOTO 32 (STA. 8+00' TO STA. 7+90')




PHOTO 33 (STA. 7+90' TO STA. 7+80')




PHOTO 34 (STA. 7+80' TO STA. 7+70')




PHOTO 35 (STA. 7+70' TO STA. 7+60')




PHOTO 36 (STA. 7+60' TO STA. 7+50')




PHOTO 37 (STA. 7+50' TO STA. 7+40')

Consultant

REPAIR NUMBER	REPAIR DESCRIPTION	REF. DETAIL/SHEET NUMBER
1	REPORT BRICK MORTAR JOINTS	1/55.01
2	BRICK REPLACEMENT (SINGLE WYTHE)	2/55.01
3	REBUILD BRICK WALL	3/55.01
4	STONE REPOINTING	4/55.01
5	DEEP STONE REPOINTING AND RESETTling	5/55.01
6	REBUILD STONE WALL RE-USING EXISTING STONE	6/55.01
7	REMOVE AND RESET COPING STONES	7/55.01
8	REPLACE MISSING COPING STONE	7/55.01
9	INSTALL NEW COPING STONE STAPLE	8/55.01
10	REMOVE AND RESET MARBLE TOMB MARKER	9/55.01

BID # 20-27

No.	Date	Description	By



**OLD BURYING GROUND
&
MT. PLEASANT CEMETERY**

**TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476**

**PHASE 1
STA. 8+20' TO STA. 7+40'
EXTERIOR & INTERIOR**

Project No. 191791.00	Checked RES	Date 2020/05/13
Drawn MAP	Approved EWF	Scale NTS
Drawing Title		
Seal		

S1.03



PHASE 2 STA. 7+40' TO STA. 5+90' EXTERIOR



PHOTO 39 (STA. 7+30' TO STA. 7+20')




PHOTO 38 (STA. 7+40' TO STA. 7+30')




PHOTO 42 (STA. 7+00' TO STA. 6+90')



PHOTO 41 (STA. 7+10' TO STA. 7+00')



PHOTO 40 (STA. 7+20' TO STA. 7+10')




PHOTO 47 (STA. 6+50' TO STA. 6+40')




PHOTO 46 (STA. 6+60' TO STA. 6+50')




PHOTO 45 (STA. 6+70' TO STA. 6+60')




PHOTO 44 (STA. 6+80' TO STA. 6+70')




PHOTO 43 (STA. 6+90' TO STA. 6+80')




PHOTO 52 (STA. 6+00' TO STA. 5+90')




PHOTO 51 (STA. 6+10' TO STA. 6+00')




PHOTO 50 (STA. 6+20' TO STA. 6+10')




PHOTO 49 (STA. 6+30' TO STA. 6+20')




PHOTO 48 (STA. 6+40' TO STA. 6+30')

Consultant

REPAIR NUMBER	REPAIR DESCRIPTION	REF. DETAIL/SHEET NUMBER
1	REPOINT BRICK MORTAR JOINTS	1/55.01
2	BRICK REPLACEMENT (SINGLE WYTHE)	2/55.01
3	REBUILD BRICK WALL	3/55.01
4	STONE REPOINTING	4/55.01
5	DEEP STONE REPOINTING AND RESETTLES	5/55.01
6	REBUILD STONE WALL RE-USING EXISTING STONE	6/55.01
7	REMOVE AND RESET COPING STONES	7/55.01
8	REPLACE MISSING COPING STONE	7/55.01
9	INSTALL NEW COPING STONE STAPLE	8/55.01
10	REMOVE AND RESET MARBLE TOMB MARKER	9/55.01

BID # 20-27

No.	Date	Description	By

**OLD BURYING GROUND
&
MT. PLEASANT CEMETERY**

**TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476**

Project

**PHASE 2
STA. 7+40' TO STA. 5+90'
EXTERIOR**


Drawing Title

Project No. 191791.00	Checked RES	Date 2020/05/13
Drawn MAP	Approved EWF	Scale NTS

Drawing No.

S2.01

Seal



PHASE 2 STA. 7+40' TO STA. 5+90' INTERIOR




PHOTO 53 (STA. 7+40' TO STA. 7+30')



PHOTO 54 (STA. 7+30' TO STA. 7+20')




PHOTO 55 (STA. 7+20' TO STA. 7+10')




PHOTO 56 (STA. 7+10' TO STA. 7+00')



PHOTO 57 (STA. 7+00' TO STA. 6+90')



PHOTO 58 (STA. 6+90' TO STA. 6+80')




PHOTO 59 (STA. 6+80' TO STA. 6+70')



PHOTO 60 (STA. 6+70' TO STA. 6+60')



PHOTO 61 (STA. 6+60' TO STA. 6+50')



PHOTO 62 (STA. 6+50' TO STA. 6+40')



PHOTO 63 (STA. 6+40' TO STA. 6+30')




PHOTO 64 (STA. 6+30' TO STA. 6+20')



PHOTO 65 (STA. 6+20' TO STA. 6+10')




PHOTO 66 (STA. 6+10' TO STA. 6+00')



PHOTO 67 (STA. 6+00' TO STA. 5+90')

Consultant

REPAIR NUMBER	REPAIR DESCRIPTION	REF. DETAIL/SHEET NUMBER
1	REPOINT BRICK MORTAR JOINTS	1/55.01
2	BRICK REPLACEMENT (SINGLE WYTHE)	2/55.01
3	REBUILD BRICK WALL	3/55.01
4	STONE REPOINTING	4/55.01
5	DEEP STONE REPOINTING AND RESETTling	5/55.01
6	REBUILD STONE WALL RE-USING EXISTING STONE	6/55.01
7	REMOVE AND RESET COPING STONES	7/55.01
8	REPLACE MISSING COPING STONE	7/55.01
9	INSTALL NEW COPING STONE STAPLE	8/55.01
10	REMOVE AND RESET MARBLE TOMB MARKER	9/55.01

BID # 20-27


No.	Date	Description	By

**OLD BURYING GROUND
&
MT. PLEASANT CEMETERY**

**TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476**

**PHASE 2
STA. 7+40' TO STA. 5+90'
INTERIOR**

Project No. 191791.00	Checked RES	Date 2020/05/13
Drawn MAP	Approved EWF	Scale NTS
Drawing Title S2.02		



PHASE 2 STA. 5+90' TO STA. 4+96' EXTERIOR




PHOTO 70 (STA. 5+68' TO STA. 5+60')




PHOTO 69 (STA. 5+80' TO STA. 5+68')




PHOTO 68 (STA. 5+90' TO STA. 5+80')




PHOTO 73 (STA. 5+40' TO STA. 5+30')




PHOTO 72 (STA. 5+50' TO STA. 5+40')




PHOTO 71 (STA. 5+60' TO STA. 5+50')




PHOTO 76 (STA. 5+10' TO STA. 4+96')




PHOTO 75 (STA. 5+20' TO STA. 5+10')




PHOTO 74 (STA. 5+30' TO STA. 5+20')

SIMPSON GUMPERTZ & HEGER
Engineering of Structures
and Building Enclosures

Simpson Gumpertz & Heger Inc.
480 Totten Pond Road
Waltham, Massachusetts 02451
Main: 781.907.9000 Fax: 781.907.9009
www.sgh.com

Boston
Chicago
Houston
Los Angeles
New York
San Francisco
Washington, DC

REPAIR NUMBER	REPAIR DESCRIPTION	REF. DETAIL/SHEET NUMBER
1	REPOINT BRICK MORTAR JOINTS	1/55.01
2	BRICK REPLACEMENT (SINGLE WYTHE)	2/55.01
3	REBUILD BRICK WALL	3/55.01
4	STONE REPOINTING	4/55.01
5	DEEP STONE REPOINTING AND RESETTING	5/55.01
6	REBUILD STONE WALL RE-USING EXISTING STONE	6/55.01
7	REMOVE AND RESET COPING STONES	7/55.01
8	REPLACE MISSING COPING STONE	7/55.01
9	INSTALL NEW COPING STONE STAPLE	8/55.01
10	REMOVE AND RESET MARBLE TOMB MARKER	9/55.01

BID # 20-27

No.	Date	Description	By

**OLD BURYING GROUND
&
MT. PLEASANT CEMETERY**

**TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476**

Project

**PHASE 2
STA. 5+90' TO STA. 4+96'
EXTERIOR**


Drawing Title


Project No. 191791.00	Checked RES	Date 2020/05/13
Drawn MAP	Approved EWF	Scale NTS

Drawing No.

S2.03

Seal



 **PHASE 2 STA. 5+90' TO STA. 4+96' INTERIOR**




PHOTO 77 (STA. 5+90' TO STA. 5+80')




PHOTO 78 (STA. 5+80' TO STA. 5+68')




PHOTO 79 (STA. 5+68' TO STA. 5+60')



PHOTO 80 (STA. 5+60' TO STA. 5+50')



PHOTO 81 (STA. 5+50' TO STA. 5+40')




PHOTO 82 (STA. 5+40' TO STA. 5+30')




PHOTO 83 (STA. 5+30' TO STA. 5+20')




PHOTO 84 (STA. 5+20' TO STA. 5+10')




PHOTO 85 (STA. 5+10' TO STA. 4+96')

SIMPSON GUMPERTZ & HEGER
Engineering of Structures
and Building Enclosures

Simpson Gumpertz & Heger Inc.
480 Totten Pond Road
Waltham, Massachusetts 02451
main: 781.907.9000 fax: 781.907.9009
www.sgh.com

Boston
Chicago
Houston
Los Angeles
New York
San Francisco
Washington, DC

Consultant

REPAIR NUMBER	REPAIR DESCRIPTION	REF. DETAIL/SHEET NUMBER
1	REPOINT BRICK MORTAR JOINTS	1/55.01
2	BRICK REPLACEMENT (SINGLE WYTHE)	2/55.01
3	REBUILD BRICK WALL	3/55.01
4	STONE REPOINTING	4/55.01
5	DEEP STONE REPOINTING AND RESETTling	5/55.01
6	REBUILD STONE WALL RE-USING EXISTING STONE	6/55.01
7	REMOVE AND RESET COPING STONES	7/55.01
8	REPLACE MISSING COPING STONE	7/55.01
9	INSTALL NEW COPING STONE STAPLE	8/55.01
10	REMOVE AND RESET MARBLE TOMB MARKER	9/55.01

BID # 20-27

No.	Date	Description	By

**OLD BURYING GROUND
&
MT. PLEASANT CEMETERY**

**TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476**

Project

**PHASE 2
STA. 5+90' TO STA. 4+96'
INTERIOR**



Drawing Title

Project No. 191791.00	Checked RES	Date 2020/05/13
Drawn MAP	Approved EWF	Scale NTS

Drawing No.

S2.04

Seal



PHASE 3 STA. 4+48' TO STA. 3+10' EXTERIOR




PHOTO 99 (STA. 3+20' TO STA. 3+10')




PHOTO 98 (STA. 3+30' TO STA. 3+20')



PHOTO 97 (STA. 3+40' TO STA. 3+30')



PHOTO 96 (STA. 3+50' TO STA. 3+40')




PHOTO 95 (STA. 3+60' TO STA. 3+50')




PHOTO 88 (STA. 4+30' TO STA. 4+20')




PHOTO 87 (STA. 4+40' TO STA. 4+30')




PHOTO 86 (STA. 4+48' TO STA. 4+40')



PHOTO 91 (STA. 4+00' TO STA. 3+90')




PHOTO 90 (STA. 4+10' TO STA. 4+00')




PHOTO 89 (STA. 4+20' TO STA. 4+10')




PHOTO 94 (STA. 3+70' TO STA. 3+60')




PHOTO 93 (STA. 3+80' TO STA. 3+70')




PHOTO 92 (STA. 3+90' TO STA. 3+80')

Consultant

REPAIR NUMBER	REPAIR DESCRIPTION	REF. DETAIL/SHEET NUMBER
1	REPOINT BRICK MORTAR JOINTS	1/55.01
2	BRICK REPLACEMENT (SINGLE WYTHE)	2/55.01
3	REBUILD BRICK WALL	3/55.01
4	STONE REPOINTING	4/55.01
5	DEEP STONE REPOINTING AND RESETTING	5/55.01
6	REBUILD STONE WALL RE-USING EXISTING STONE	6/55.01
7	REMOVE AND RESET COPING STONES	7/55.01
8	REPLACE MISSING COPING STONE	7/55.01
9	INSTALL NEW COPING STONE STAPLE	8/55.01
10	REMOVE AND RESET MARBLE TOMB MARKER	9/55.01

BID # 20-27

No.	Date	Description	By

**OLD BURYING GROUND
&
MT. PLEASANT CEMETERY**

**TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476**



**PHASE 3
STA. 4+48' TO STA. 3+10'
EXTERIOR**

Project No. 191791.00	Checked RES	Date 2020/05/13
Drawn MAP	Approved EWF	Scale NTS

Drawing Title

Seal

S3.01



PHASE 3 STA. 3+10' TO STA. 1+60' EXTERIOR



PHOTO 101 (STA. 3+00' TO STA. 2+90')




PHOTO 100 (STA. 3+10' TO STA. 3+00')




PHOTO 103 (STA. 2+80' TO STA. 2+70')




PHOTO 102 (STA. 2+90' TO STA. 2+80')




PHOTO 108 (STA. 2+30' TO STA. 2+20')




PHOTO 107 (STA. 2+40' TO STA. 2+30')



PHOTO 106 (STA. 2+50' TO STA. 2+40')



PHOTO 105 (STA. 2+60' TO STA. 2+50')




PHOTO 104 (STA. 2+70' TO STA. 2+60')




PHOTO 113 (STA. 1+70' TO STA. 1+60')




PHOTO 112 (STA. 1+80' TO STA. 1+70')



PHOTO 111 (STA. 1+90' TO STA. 1+80')




PHOTO 110 (STA. 2+10' TO STA. 2+00')




PHOTO 109 (STA. 2+20' TO STA. 2+10')

Consultant

REPAIR NUMBER	REPAIR DESCRIPTION	REF. DETAIL/SHEET NUMBER
1	REPOINT BRICK MORTAR JOINTS	1/55.01
2	BRICK REPLACEMENT (SINGLE WYTHE)	2/55.01
3	REBUILD BRICK WALL	2/55.01
4	STONE REPOINTING	4/55.01
5	DEEP STONE REPOINTING AND RESETTling	5/55.01
6	REBUILD STONE WALL RE-USING EXISTING STONE	6/55.01
7	REMOVE AND RESET COPING STONES	7/55.01
8	REPLACE MISSING COPING STONE	7/55.01
9	INSTALL NEW COPING STONE STAPLE	8/55.01
10	REMOVE AND RESET MARBLE TOMB MARKER	9/55.01

BID # 20-27


No.	Date	Description	By

**OLD BURYING GROUND
&
MT. PLEASANT CEMETERY**

**TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476**

**PHASE 3
STA. 3+10' TO STA. 1+60'
EXTERIOR**

Project No. 191791.00	Checked RES	Date 2020/05/13
Drawn MAP	Approved EWF	Scale NTS
Drawing No.		
S3.02		
Seal		



PHASE 3 STA. 1+60' TO STA. 0+00' EXTERIOR




PHOTO 115 (STA. 1+50' TO STA. 1+40')




PHOTO 114 (STA. 1+60' TO STA. 1+50')



PHOTO 120 (STA. 1+00' TO STA. 0+90')



PHOTO 119 (STA. 1+10' TO STA. 1+00')




PHOTO 118 (STA. 1+20' TO STA. 1+10')



PHOTO 117 (STA. 1+30' TO STA. 1+20')




PHOTO 116 (STA. 1+40' TO STA. 1+30')




PHOTO 125 (STA. 0+50' TO STA. 0+40')




PHOTO 124 (STA. 0+60' TO STA. 0+50')




PHOTO 123 (STA. 0+70' TO STA. 0+60')




PHOTO 122 (STA. 0+80' TO STA. 0+70')




PHOTO 121 (STA. 0+90' TO STA. 0+80')




PHOTO 129 (STA. 0+10' TO STA. 0+00')




PHOTO 128 (STA. 0+20' TO STA. 0+10')




PHOTO 127 (STA. 0+30' TO STA. 0+20')




PHOTO 126 (STA. 0+40' TO STA. 0+30')

Consultant

REPAIR NUMBER	REPAIR DESCRIPTION	REF. DETAIL/SHEET NUMBER
1	REPOINT BRICK MORTAR JOINTS	1/55.01
2	BRICK REPLACEMENT (SINGLE WYTHE)	2/55.01
3	REBUILD BRICK WALL	3/55.01
4	STONE REPOINTING	4/55.01
5	DEEP STONE REPOINTING AND RESETTling	5/55.01
6	REBUILD STONE WALL RE-USING EXISTING STONE	6/55.01
7	REMOVE AND RESET COPING STONES	7/55.01
8	REPLACE MISSING COPING STONE	7/55.01
9	INSTALL NEW COPING STONE STAPLE	8/55.01
10	REMOVE AND RESET MARBLE TOMB MARKER	9/55.01


BID # 20-27

No.	Date	Description	By

**OLD BURYING GROUND
&
MT. PLEASANT CEMETERY**

**TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476**
Project


PHASE 3 STA. 1+60' TO STA. 0+00' EXTERIOR		
Drawing Title		
Project No. 191791.00	Checked RES	Date 2020/05/13
Drawn MAP	Approved EWF	Scale NTS
Seal		
S3.03		




- REPOINTING NOTES:
1. REMOVE EXISTING MORTAR FROM JOINT WITHOUT CHIPPING OR DAMAGING BRICK.
 2. REMOVE DIRT AND DEBRIS FROM JOINT. RINSE JOINT WITH WATER.
 3. APPLY MORTAR IN $\frac{3}{8}$ " LIFTS AND ALLOW TO DRY TO THUMBPRINT HARD BEFORE APPLYING SUBSEQUENT LAYER.
 4. TOOL FINAL LIFT TO MATCH PROFILE AND APPEARANCE OF (E) MORTAR JOINTS. TEXTURE TO A UNIFORM "SAND" FINISH.
 5. MOIST CURE MORTAR FOR AT LEAST 72 HOURS. COVER WITH TARPS TO SHIELD FROM SUN AND WIND DURING CURING.

AREA OF SINGLE WYTHE REPLACEMENT BRICK

- REPAIR NOTES:
1. REMOVE EXISTING OUTER WYTHE OF MASONRY IN AREA OF SPALLED BRICK WITHOUT DAMAGING BRICK TO REMAIN.
 2. REMOVE MORTAR FROM SECOND WYTHE OF BRICK AND REPOINT.
 3. USING BRICK TO MATCH EXISTING BRICK, REBUILD OUTER WYTHE OF BRICK TO MATCH PATTERN AND COURSING OF ORIGINAL MASONRY.
 4. TOOL JOINTS TO MATCH ORIGINAL MORTAR JOINTS.



- NOTES:
1. ALL DIMENSIONS AND EXISTING GRADE VARY. VERIFY ALL DIMENSIONS IN FIELD (V.I.F.).
 2. STABILIZE AND PROTECT (E) GRADE ADJACENT TO (E) BRICK WALL PRIOR TO DEMOLITION AND DURING CONSTRUCTION.
 3. THE BASE OF THE (E) BRICK WALL WAS NOT VISIBLE DURING INVESTIGATION PHASE. (E) BASE MAY NEED TO BE RESET BEFORE (E) BRICK WALL IS REBUILT.




- REPOINTING NOTES:
1. REMOVE EXISTING MORTAR FROM JOINT WITHOUT CHIPPING OR DAMAGING STONE.
 2. REMOVE DIRT AND DEBRIS FROM JOINT. RINSE JOINT WITH WATER.
 3. APPLY MORTAR IN $\frac{3}{8}$ " LIFTS AND ALLOW TO DRY TO THUMBPRINT HARD BEFORE APPLYING SUBSEQUENT LAYER.
 4. WHEN FINAL LIFT IS APPLIED, TOOL TO MATCH JOINT PROFILE SHOWN.
 5. MOIST CURE MORTAR FOR AT LEAST 72 HOURS. COVER WITH TARPS TO SHIELD FROM SUN AND WIND DURING CURING.
 6. REPOINT ALL MORTAR UNDER COPING STONES. WHERE NECESSARY, REMOVE SMALL STONES INHIBITING REPAIR.
 7. IF MORTAR REMOVAL BEYOND 3" IS NECESSARY, SEE DETAIL 5/55.01 FOR DEEP REPOINTING.

1 BRICK REPOINTING

2 BRICK REPLACEMENT (SINGLE WYTHE)





3 REBUILT BRICK WALL

4 STONE REPOINTING



DEEP REPOINTING NOTES:

1. REMOVE EXISTING MORTAR FROM JOINT WITHOUT CHIPPING OR DAMAGING STONE.
2. REMOVE AND RESET LOOSE STONES AND PROVIDE SHIMS AS NECESSARY.
3. REMOVE DIRT AND DEBRIS FROM JOINTS. RINSE JOINT WITH WATER.
4. APPLY MORTAR IN $\frac{3}{8}$ " LIFTS AND ALLOW TO DRY TO THUMBPRINT HARD BEFORE APPLYING SUBSEQUENT LAYER.
5. TOOL FINAL LIFT TO MATCH PROFILE AND APPEARANCE OF (E) MORTAR JOINTS.
6. MOIST CURE MORTAR FOR AT LEAST 72 HOURS. COVER WITH TARPS TO SHIELD FROM SUN AND WIND DURING CURING.
7. REPOINT ALL MORTAR UNDER COPING STONES. WHERE NECESSARY, REMOVE SMALL STONES INHIBITING REPAIR.



5A PARTIAL ELEVATION

5B SECTION





7A BRICK WALL

7B STONE WALL

5 DEEP REPOINTING AND RESETTING LOOSE STONES

6 REBUILT STONE WALL

7 RESET COPING STONES



8A PLAN VIEW

8B SECTION

9 RESET MARBLE TOMB MARKER

10 STONE DUTCHMAN REPAIR

8 COPING STONE STAPLES

Consultant

BID # 20-27

No.	Date	Description	By

OLD BURYING GROUND & MT. PLEASANT CEMETERY

TOWN OF ARLINGTON
730 MASSACHUSETTS AVE.
ARLINGTON, MA 02476

Project

REPAIR DETAILS

Drawing Title

Project No. 191791.00	Checked RES	Date 2020/05/13
Drawn MAP	Approved EWF	Scale NTS

S5.01

Seal